

**An Innovative Hybrid ICF System
Offering an Ingenious Lineup of Interchangeable
Preformed and Site-Assembled Blocks.**


ElementICF.com

© Copyright Logix Brands Ltd. (2023) All rights reserved.


No part of the work contained herein as covered by this copyright may be reproduced or used in any form, or any means – graphic, electronic or mechanical, including without limitation photocopying. By using these products, you agree to assume all risks associated therewith. See LogixBrands.com/Disclaimer-General for a full copy of disclaimer.

A PRODUCT BY
LOGIX[®]
BRANDS


ELEMENT PREFORMED BLOCKS STANDARDS AND 90 DEGREE CORNERS (6" AND 8" CONCRETE CORES)




■ ELEMENT'S PREFORMED BLOCKS ARE FULLY INTERCHANGEABLE with site-assembled blocks.



■ THE WEB USED IN ELEMENT'S PREFORMED BLOCKS.



■ PREFORMED BLOCKS HAVE THE ZIP TABS that securely clip the blocks top-to-bottom to minimize lifting and settling.



■ A BRIDGING FLEXTIE will perma-lock two preformed 90 degree corner forms together.

■ REGULAR FLEXTIES are used to provide additional diagonal corner support.

ASK US
ANYTHING
>>> 24/7




ELEMENT SITE-ASSEMBLED BLOCKS

(QUICKLY MADE WITH PANELS & FLEXTIES)




STANDARD




TAPER TOP



BRICK LEDGE





90 DEGREE
CORNER



AND 1 INGENUOUS FLEXTIE™

- **DESIGNED FOR LIGHTNING FAST INSTALLATION**, Element's Flexties have no top, bottom, front or back.

- Flexties securely lock into place to create rugged easy-to-handle blocks.



The same Flextie also provides diagonal corner support.

SITE-ASSEMBLED 90 DEGREE CORNER BLOCK


ASK US
ANYTHING
>>> 24/7



A WIDE RANGE OF CONCRETE CORE WIDTHS



- FLEXTIES ARE AVAILABLE IN A WIDE RANGE OF CORE WIDTHS.



- SITE-ASSEMBLED BRICK LEDGE, TAPER TOP AND DOUBLE TAPER TOP BLOCKS ARE AVAILABLE IN ALL CORE WIDTHS.

ASK US
ANYTHING
>>> 24/7



ROBUST REVERSIBLE INTERLOCK



- **ROBUST & DURABLE INTERLOCK PROVIDES A SNUG EASY FRICTION FIT**

— to minimize movement during concrete placement.


- **4 WAY REVERSIBLE INTERLOCK MEANS OUR BLOCKS HAVE NO TOP OR BOTTOM, FRONT OR BACK**

— product waste is reduced.

- **SELF DRAINING TO MINIMIZE ICE BUILD-UP IN COLD CONDITIONS.**

- **NO LEFT AND RIGHT CORNERS**


— this saves time on the job site.



**ASK US
ANYTHING
>>> 24/7**



UNMATCHED STRENGTH & STABILITY




■ **2 3/4" FOAM PANELS ARE THICKER AND STRONGER THAN MOST.**

■ **90 DEGREE CORNER BLOCKS HAVE 2 WEBS ON THE SHORT LEG AND 4 ON THE LONG.** Plus an additional diagonal support web at the intersecting corner.


■ **NO ICF 90 CORNER BLOCK OFFERS MORE WEB SUPPORT.** Greatest strength is provided at the corners where it is needed most.

■ **ABUNDANT FASTENING SURFACES AT EVERY CORNER.**

■ **WEBS ALWAYS CLIP TOGETHER** — so no floating or settling occurs during the concrete pour. Plus - the need for wire clips or gluing is eliminated!




■ **AND WHEN THE NEED FOR ABSOLUTE MAXIMUM STRENGTH IS ESSENTIAL** — a “bridging flextie” placed in the end-locking channels will “perma-lock” one course to the other!




ASK US ANYTHING >>> 24/7



TRUSTED FUNDAMENTALS



- **4' BLOCK LENGTH** — the optimum length for fast & easy handling & installation.
- **16" BLOCK HEIGHT** — conforms to accepted industry standards.
- **THICK 2 3/4" FOAM PANELS** — provide added strength and more R-value.



- **1 1/2" WIDE FURRING STRIPS EVERY 8" O/C**

- **CONVENIENT HORIZONTAL CUT LINES EVERY 4"**—save time and reduce errors and waste.
- **1" VERTICAL CUT LINES PROVIDE MORE OPTIONS TO CUT BLOCKS** without having to support stacked seams. (2" cut lines at the furring strips)

**ASK US
ANYTHING
>>> 24/7**




TRUSTED FUNDAMENTALS



■ **RUGGED REBAR HOLDERS**
allow a single crew member to install longer rebar lengths.



■ **OPEN WEB DESIGN**
optimizes concrete flow and consolidation.



■ **ALL-FOAM WIRE CHASES**
provided every 16" o/c horizontally.
No plastic or metal to cut through to install wiring.

■ **CONTINUOUS WEBS**— No settling

■ **NO GROOVES CUT INTO THE INTERIOR WALLS**
—this preserves system R-value.




**ASK US
ANYTHING
>>> 24/7**




BUILDING TO 4" HEIGHT INCREMENTS IS SIMPLE

Simply use 4" Height Adjusters.




■ 4' LONG


■ 4" TALL



■ INSERT BRIDGING FLEXTIES



■ THE HEIGHT ADJUSTER'S ZIP TABS CLIP into the courses above and below.



■ HEIGHT ADJUSTERS ALSO PERMA-LOCK INTO PLACE with the bridging Flexties.

■ HEIGHT ADJUSTERS ALSO HAVE THE 1 1/2" FURRING STRIPS.

■ **ALTERNATIVE INSTALLATION TIP** - Instead of installing the bridging Flexties, you can snap Flexties in half at the scored center point and cross-brace the opposing height adjusters with the 1/2 Flextie pieces.

ASK US ANYTHING >>> 24/7




MAKING HALF HEIGHT (8") BLOCKS IS SIMPLE TOO!




TO CREATE TWO FULLY FUNCTIONAL 8" TALL BLOCKS SIMPLY:


1 Snap Flexties in half at the scored center point.




2 Slide an inverted 1/2 Flextie piece into each end locking position in the block.




3 The 1/2 Flexties securely lock into place.






4 Cut the 16" tall block in half along the embossed center cut line.



5 You now have two rugged and fully functional 8" tall blocks with zero waste created.



Alternative Installation Tip - You can also create an 8" tall block with 4 Height Adjusters and 6 Flexties.



ASK US ANYTHING >>> 24/7




SIMPLIFIED WALL OPENINGS

PRO BUCK™




- **EASY, VOID-FREE CONCRETE PLACEMENT UNDER THE OPENING** — foam-only areas for 4" access holes.
- **STRONG, SECURE, RELIABLE FASTENING** — high-strength exposed furring strips.
- **CONCRETE ANCHORS EVERY 8" O/C** — ensure a solid connection to the concrete wall and provide a chair for horizontal rebar placement.



- **FAST PICTURE FRAMING TO THE INTERNAL FLANGES EVERY 8" O/C** — (that do not have to be removed for finishing!)

- **STRONG, DEPENDABLE, INSULATING FOAM** — high-density 2 lb. foam.

- **MINIMAL WASTE** — leftover pieces securely clip together end-to-end, generating minimal waste.




ASK US ANYTHING
»» 24/7





ADD ADDITIONAL R-VALUE WITH XRV™ PANELS

(PATENT PENDING)




■ **START WITH REGULAR STANDARD PANELS**



■ **XRV™ PANEL LOCKS INTO PLACE** (adding additional R-8 R-value)

■ **REGULAR FLEXTIES** complete the site-assembled XRV™ block.

■ **THE FURRING STRIPS** always remain just beneath the foam surface for fast and secure fastening of finishes.



■ **ADDITIONAL DESIGN TIP** - Additional XRV™ panels can be locked into place on either side to create virtually unlimited R-value solutions.



ASK US ANYTHING
 >>> 24/7



BEST IN CLASS PACKAGING



Many dealers consider ordinary ICFs to be a nuisance product.



ELEMENT ICF OFFERS BEST IN CLASS PACKAGING

- **ALL PRODUCTS ARE PACKAGED** in easy-to-handle color-coded porta-cubes and bags with UV-resistant wrap.
- **THE PORTA-CUBES AND BAGS ARE SKIDDED AND SHRINK-WRAPPED.**
- **EASY-TO-HANDLE UV-PROTECTED CUBES** are shipped on skids and can be stored outside.
- **A SIMPLIFIED SYSTEM** that is easy to understand, explain, price and sell.
- **UP TO 1,296 BLOCK PER FTL.**
- **SHIPS EFFICIENTLY AND SAFELY ON FLATBEDS.**



ASK US ANYTHING
»» 24/7



WANT TO BUILD A HIGH-PERFORMANCE FOUNDATION, HOME OR BUILDING?


BUILT-IN COST-SAVINGS!

Six construction steps.
One simple package.

- = Less labor
- = Lower construction costs
- = Faster builds


CONSTRUCTION STEPS

- 1 CONCRETE
- 2 STEEL REINFORCEMENT
- 3 INSULATION
- 4 AIR BARRIER
- 5 VAPOR BARRIER
- 6 FURRING STRIPS



BUILT-IN ENERGY-SAVERS!


- THREE built-in energy-saving factors deliver up to 50% energy savings.



- 1 Two 2.75" thick panels of continuous foam insulation.
- 2 An air-tight wall assembly.
- 3 The temperature moderating thermal mass of concrete.

In a recent lab test, when exposed to a sudden -31°F temperature, an ICF wall allowed the temperature of the interior chamber to maintain at a comfortable 70°F for a full two days without the heat source even turning on once! (With a wood wall the heater turned on almost immediately.)

LEARN MORE!



Thermal image of a conventionally built home.





Thermal image of a home built with ICFs.

KEEP IT SIMPLE.™

BUILT-IN RESILIENCE!

- **Wind Protection**
Wind-rated to over 300 mph
- **Fire Protection**
4-hour fire rating
- **Earthquake Protection**
Engineering available for all seismic zones
- **Moisture Protection**
Does not rot!



Outside noise is reduced to a whisper.

BUILT-IN COMFORT!

- Drafts and cold spots in the home are eliminated in northern climates.
- Humidity is easily controlled in warm, moist climates.
- EPS foam and concrete do not off-gas unhealthy, allergy-aggravating emissions.
- No nutrient source exists in the Element ICF wall assembly for unhealthy mold growth.



CONNECT WITH A LOCAL MANUFACTURER

888.838.5038

330 Cain Drive
Haysville, KS 67060-2004

888.453.5961

11581-272 St.
Acheson, AB T7X 6E9

888.706.7709


840 Division St.
Cobourg, ON K9A 5V2

888.453.5961

215-44393 Simpson Rd,
Chilliwack, British Columbia
Canada V2R 5M3

877.789.7622

35 Headingley Rd.
Headingley, MB R4H 0A8



ELEMENTICF[®]

info@elementicf.com
ElementICF.com

A PRODUCT BY
LOGIX[®]
BRANDS